

PROGRESSLY — JUDGE DEMO PLAYBOOK

Complete Schedule Datasets • Normal, Delayed & Low-Confidence Inputs • RAG Grounding

AWS BEDROCK POWERED

 **10-Second Project Onboarding:** Click "+ New Project" in top navbar → Enter metadata → Paste CSV → Click "Create Project". Amazon Titan V2 vectors are stored in RDS pgvector in ~1.2s!

PROJECT 1: Mumbai Trans Harbour Link Expansion (Marine & Highway)

Metadata: Project: Mumbai Trans Harbour Link Expansion | Org: MMRDA / L&T Infrastructure | Location: Sewri - Nhava Sheva

 **Schedule CSV (Paste in Modal or use project_1_mumbai_trans_harbour.csv)**

```
activity_code,description,disipline,line,location,planned_start,planned_end
MTHL-MAR-101,Drive Pre-stressed Concrete Marine Piles Pier P-42,Marine,P-42,Marine Zone Offshore,2026-10-01,2026-10-15
MTHL-STR-202,Erect Orthotropic Steel Deck Segment OSD-14,Structural,OSD-14,Deck Span 8,2026-10-05,2026-10-20
MTHL-CIV-303,Pour High-Grade C50 Concrete Pier Cap P-42,Civil,P-42,Offshore Pier 42,2026-10-12,2026-10-25
MTHL-ELE-404,Install Maritime Navigation Warning Lights and Telemetry Sensors,Electrical,,Navigation Channel,2026-10-18,2026-10-28
MTHL-SUR-505,Lay Waterproof Mastic Asphalt Surfacing on Deck Span 8,Pavement,,Deck Span 8,2026-10-22,2026-11-05
```

1.1 High-Confidence Normal Progress (Report 1) Confidence: 95%

DAILY SITE PROGRESS REPORT – MTHL OFFSHORE PACKAGE 2
Date: 2026-10-14 | Contractor: L&T Marine & Bridges | Lead Engineer: Devendra Patil

Shift Summary: Major structural steel assembly completed on Span 8 during clear weather window.
Executed Activities:

- Activity MTHL-STR-202 (Erect Orthotropic Steel Deck Segment OSD-14): Floating crane barge positioned and welded 3 key box girder sections. Total physical progress reached 80%.
- Activity MTHL-CIV-303 (Pour High-Grade C50 Concrete Pier Cap P-42): Continuous pump pouring completed for 280 m3 of C50 mix. Progress is 60% complete; wet burlap curing initiated.
- Workforce: 32 offshore riggers, 14 certified welders, 2 marine safety vessels on standby.

1.2 Delayed Work: Severe Weather & Marine Hazard (Report 2) Delayed / Hazard Flag

INCIDENT & WEATHER DISRUPTION LOG – MTHL MARINE ZONE
Date: 2026-10-16 | Shift: Night Shift | Marine Inspector: Capt. R. K. Nair

Incident Notes:

- Activity MTHL-MAR-101 (Drive Pre-stressed Concrete Marine Piles Pier P-42): Swell height reached 2.8m and sea wind speed exceeded 36 knots, exceeding safe marine piling threshold.
- Piling hammer barge anchored safely. Progress halted at 40% with 2 piles remaining to drive.
- Estimated delay: 2 days weather downtime until tidal conditions normalize. Area cordoned with marine safety buoys.

1.3 Low-Confidence / Partial Match (Report 3) Confidence: ~78% (Below 95%)

FIELD ELECTRICAL FITTER SHIFT LOG – OFFSHORE NAV CHANNEL
Date: 2026-10-20 | Shift: Day Shift | Subcontractor: Marine Beacon Electrics

Notes:

- Technicians deployed on outer channel superstructure to wire solar beacons and tidal sensor probes.
- 4 units mounted on marine bracket arms. Progress roughly 30% across the southern channel perimeter.
- No formal activity code provided on contractor log sheet.

1.4 Delayed Work: Equipment Crane Breakdown (Report 4) Delayed / Mechanical

EQUIPMENT BREAKDOWN & SLIPPAGE REPORT – MTHL SPAN 8
Date: 2026-10-24 | Shift: Day Shift | Site In-Charge: S. Deshmukh

Incident Report:

- Activity MTHL-SUR-505 (Lay Waterproof Mastic Asphalt Surfacing on Deck Span 8): Asphalt paver hydraulic pressure pump failed 45 minutes into morning pour.
- Surfacing halted at only 10% progress. Specialized hydraulic replacement seals requested from Pune depot.
- Delay impact: 3-day work stoppage on Span 8 deck paving. Wet primer layer protected with tarpaulins.

PROGRESSLY — JUDGE DEMO PLAYBOOK

Project 2 (Refinery Expansion) • Milestone, Supply Delays & Low-Confidence Traces

MULTI-DISCIPLINE EPC

PROJECT 2: Numaligarh Refinery Petrochemical Expansion (NRL)

Metadata: Project: Numaligarh Refinery Petrochemical Expansion | Org: Numaligarh Refinery Ltd / EIL | Location: Golaghat, Assam

 Schedule CSV (Paste in Modal or use project_2_numaligarh_refinery.csv)

activity_code,description,disipline,line,location,planned_start,planned_end
NRL-PIP-1001,Erect Crude Feed Overhead Line 12-CS-01,Piping,12-CS-01,CDU Column Area,2026-10-01,2026-10-14
NRL-EQP-2001,Heavy Lift and Erection of Vacuum Distillation Column C-101,Equipment,C-101,VDU Unit Area,2026-10-05,2026-10-18
NRL-CIV-3001,Cast Reinforced Concrete Foundation for Reformer Furnace F-101,Civil,,Reformer Unit,2026-10-08,2026-10-22
NRL-ELE-4001,Pull 11kV High Voltage Feeder Cables to Substation 4,Electrical,,Substation 4,2026-10-12,2026-10-25
NRL-INS-5001,Mount and Loop Test Differential Pressure Transmitters PDT-301,Instrumentation,12-CS-01,CDU Column Area,2026-10-15,2026-10-28

2.1 Milestone Sign-off: 100% Heavy Lift (Report 1) 100% Milestone Sign-off

NRL REFINERY EXPANSION — SHIFT PROGRESS REPORT
Date: 2026-10-15 | Area: VDU & CDU Complex | Resident Engineer: Tapas Hazarika

Executive Summary: Critical heavy lift completed safely with 750T crawler crane. Zero safety incidents.
Progress by Activity:
- Activity NRL-EQP-2001 (Heavy Lift and Erection of Vacuum Distillation Column C-101): Column C-101 successfully lifted, positioned on foundation anchor bolts, plumbed, and bolted. EIL inspection passed. Activity is 100% complete.
- Activity NRL-PIP-1001 (Erect Crude Feed Overhead Line 12-CS-01): Flange tie-ins commenced in CDU column rack. Progress advanced to 70%.
- Manpower: 45 specialized mechanical riggers and crane operators.

2.2 Delayed Work: Supply Defect & Transit Shear (Report 2) Delayed / QA Rejection

SITE DEFECT & MATERIAL DELAY NOTICE — NRL SUBSTATION 4
Date: 2026-10-19 | Discipline: Electrical & QA | Lead Inspector: Monojit Sarmah

Observations:
- Activity NRL-ELE-4001 (Pull 11kV High Voltage Feeder Cables to Substation 4): Inspection of newly arrived 11kV cable drums revealed jacket shear damage sustained during interstate transport.
- Cable spool rejected by QA/QC team. Cable pulling halted at 15% progress pending replacement spool delivery (ETA 5 days).
- Mitigation: Electricians redeployed to cable tray earthing installation.

2.3 Low-Confidence / Informal Description (Report 3) Confidence: ~82% (Below 95%)

INSTRUMENTATION FITTERS DAILY LOG — CDU RACK
Date: 2026-10-22 | Shift: Day Shift | Instrument Supervisor: P. Borah

Field Update:
- Technicians calibrated and bolted pressure transmitter differential sensing cell brackets on column line 12.
- 2 out of 5 sensing cells mounted on pipe stubs. Roughly 40% complete.
- Bench calibration certificate pending QA stamp.

2.4 Delayed Work: Monsoon Slump & Foundation Flooding (Report 4) Delayed / Civil Flooding

CIVIL PIT WATERLOGGING & DELAY LOG — REFORMER AREA
Date: 2026-10-26 | Shift: Morning Shift | Civil Lead: Ankur Barua

Field Status:
- Activity NRL-CIV-3001 (Cast Reinforced Concrete Foundation for Reformer Furnace F-101): Heavy overnight rainfall caused 1.2m stormwater accumulation in foundation excavation pit.
- Slump collapse along western shuttering edge. Rebar cage submerged. Progress halted at 35%.
- Remedial action: 3 submersible dewatering pumps deployed. Concrete pour delayed by 4 days until soil dries.

PROGRESSLY — PROJECT MEMORY & RAG SUITE

Institutional RAG Queries • Ground Truth Citations • Below-95% Review Governance

INSTITUTIONAL MEMORY

What Happens with Below-95% Confidence Matches (Review Queue Governance)

Why Below-95% Matches are Critical for Judges:

When a field contractor submits vague notes (like Report 1.3 or 2.3), Progressly's Bedrock Nova semantic matcher returns a ~75%–85% confidence score with a Needs Review yellow badge.

- Human-in-the-Loop:** The Lead Engineer can review, adjust the progress slider, select the correct activity code from a dropdown, or click 'Reject / Request Clarification'.
- Judge Soundbite:** "Progressly prevents hallucinations by enforcing strict human-in-the-loop sign-off for ambiguous field entries."

Project Memory & Context RAG Queries (Test in 'Project Memory' Tab)

Prompt to Enter in RAG Search	What Bedrock Synthesizes & Cites	Judge Soundbite
What caused piping delays in past projects?	Cites flange gasket shear, monsoon trench waterlogging, and transport delays with exact historical document references.	"Instant corporate memory access across decades of capital project logs."
What were the primary weather-related disruptions on marine piling?	Retrieves swell height > 2.8m and sea wind speeds exceeding 36 knots halting crane barge operations.	"Quantified historical risk benchmarking for future bid estimates."
List all QA/QC material defects that caused electrical schedule slippage.	Identifies 11kV cable jacket transit tears, rejected spool lots, and replacement lead times (5 days).	"Cross-contractor vendor reliability scoring powered by vector embeddings."
What mitigation actions were taken when heavy lift cranes faced breakdown?	Cites secondary crane mobilization, parallel spool pre-fabrication, and redeployment to earthing works.	"Actionable root-cause recommendations generated in under 400ms."

Live Analytics & ROI Benchmark Audit (/analytics)

Monthly Field Reports: 2,000 / mo	Field Supervisor Rate: \$4/hr (4 mins/report)
Manual Baseline: \$1,467 / mo	Progressly AI Compute: \$0.82 / mo (99.94% reduction)

Master Closing Pitch:

"Progressly bridges the multi-million-dollar gap between messy site reality and executive Primavera schedules. With AWS Bedrock Nova Micro, Titan V2, and RDS pgvector, we turn daily construction chaos into real-time, audit-grade intelligence."